BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2017-18/OW/WORK_INDENT26725

APPROVED SCHEDULE - B

E/BTP/BBMP/E-PMT/05/2017-18, Date: 17.08.2017

Preparation of immersion tank in Rachenahalli lake in ward no. 07 Byatarayanapura

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Manjunath A	
				In Figures	In Words
1	110	Supply of Drinking Water through water tankers of Capacity 6000 Liters and Hiring of Water Tanker Hiring of Tractor 40HP including cost of warer and Engaging Heavy Mazdoor to deliver water including cost of fuel lubricants men and machinary etc. complete including	each	538.39	Rupees Five Hundred Thirty Eight and Thirty Nine Paise Only
2	1400	Earthwork and removal of silt or silt mixed with sand in slushy condition from canal bed including jack well disposing of the same in spoil bank or on canal emebankment in layers as directed etc., complete with initial lead upto 50m and all lifts	cum	109.15	Rupees One Hundred Nine and Fifteen Paise Only
3	11	HOM for pumping of 3.5 KL/Hr capacity pump	Hr	52.48	Rupees Fifty Two and Forty Eight Paise Only
4	144.4	Earthwork excavation in oriidnary soil for levelling and lowering the ground manually (Other than foundation of buildings culverts road and treches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m excavated surface levelled and neatly dressed disposed earth to be lvelled after breaking clods and neatly dressed as per specifications., Specification	cum	174.66	Rupees One Hundred Seventy Four and Sixty Six Paise Only
5	92.5	Supplying and spreading stone dust for the existing surface to fix shamiyana etc.,	cum	839.6	Rupees Eight Hundred Thirty Nine and Sixty Paise Only
6	1650	Hire Charge for supplying and running circuit service main with necessary messanger wire and reel insulators and maintaining the same 4 of 25 sqmm PVC insulated and sheathedaluminium wire	M	9.45	Rupees Nine and Forty Five Paise Only
7	275	Providing Causal Labours (Unskilled mazdoor Heavy)	Nos	271.69	Rupees Two Hundred Seventy One and Sixty Nine Paise Only
8	75	Hire charge of 100 KVA Generator including operator, Fuel, transportation and Handling charges	Hr	661.19	Rupees Six Hundred Sixty One and Nineteen Paise Only
9	1540	Lead for diposal of debris shall be payable at carriage rates mechanical means including loading and unloading .	cum	82.76	Rupees Eighty Two and Seventy Six Paise Only

Signature of the Contractor

29/01

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92